

I... um I

Technical Rider

Version: RV 2023 05 15

TIME SCHEDULE

Arrival & build up 7 hours before commencement, possible breaks in consultation

Performance Approx. 60 minutes, without pause. Hall doors and start in consultation with theatre.

Breaking down Approx. 3 hours

When a set of shows is in order, time agreements will be made by phone

STAFF

Company The company consists of 4 technicians, 1 truck driver and 3 actors.

Theatre 3 experienced technicians from the theatre.

TECHNICAL INFORMATION

Audio The company brings their own audio console, 9 wireless microphones in B-band channels and cables

Own audio system flown above the stage (in addition with pa system of the theatre)

Light Minimal 40x 2kw DMX dimmers, own light computer. A 2nd dmx line from foh to stage right.

Power 2x 32A/380V on stage right, 1x 16A/230V on stage right

Transport Truck + citytrailer: L 14.23 mtr. - H 4.00 mtr - W 2.59 mtr | Inside: 11.18 - 2.65 - 2.48 Parking apreciated

And 3 cars from crew. Parking apreciated

Cargo elevator (if relevant) Minimum size for decor trolleys: L 3.25 mtr - H 2.35 mtr - W 1.00 mtr

STAGE SET UP

Decor/set A spinning living room. We will bring a truss construction for lights and build up of the living room.

For the construction of the trusscarre (2.5 x 6.5 meters, 5.20 high) well use the theater's hoisting

facilities.

Play floor Minimum size 10 x 10 x 6 high

Sightlines Given the shape of the set, sightlines are very important. See drawing added.

Blockades and sightlines (see drawing): Your Marketing team is fully informed about this.

Masking Complete black masking around stage floor.

Marley dance floor Black Marley dance floor taped down from front stage to backdrop.

Cabin Seats for technicians in the audience (light and audio). No use of cabin.

COMPANY INFORMATION

Technical Tjarko van Heese, + 31 6 50 56 38 10, tjarko@hethoutenhuis.org

General HET HOUTEN HUIS, www.hethoutenhuis.org, info@hethoutenhuis.org



